

- 2. Heavy compaction machinery to be used 1.2m away from the wall face
- 3. 95% of standard Maximum Dry Density (MDD) or equivalent Clegg Impact Value (CIV)
- 4. Rollers and compactors must run parallel to the retaining wall

